



TOWN OF HOLDERNESS

NEW HAMPSHIRE

DISTANCE IN FEET FOR SEWAGE DISPOSAL SYSTEMS

	<u>Septic Tank</u>	<u>Leach Field</u>	<u>Dry Well</u>	<u>Sewer Line</u>
Surface Water (including the reference line of a lake, stream, pond or wetland)	75	125	75	
Open Drainage	75	75	75	
Culvert (tight pipe)	25	35	35	
Culvert opening	50	75	75	
Catch basins	35	35	35	
In ground pools	25	35	50	10
Private well, on -site	75	125	75	
Private well, off-site	75	125	75	
Community well	200	200	200	
Reservoirs	75	75	75	
Municipal Well	400	400	400	400
Water line, pressure	10	25	25	10
Water line, suction	50	75	75	50
Property line	35	35	35	35
Foundations				
With drains	25	35	35	
Full (no drains)	5	10	10	
Slab (no drains)	5	5	5	
Top of natural embankment or natural steep slope	5	20	20	
Interceptor drains, leaching area				
Below finished grade	50	75	75	75
Above finished grade	35	35	35	35
Property line	35	35	35	