

Town of Holderness NEW HAMPSHIRE

DISTANCE IN FEET FOR SEWAGE DISPOSAL SYSTEMS

	Septic Tank	Leach Field	<u>Dry</u> Well	Sewer Line
Surface Water 75 125 75 (including the high water line of a lake, stream, pond or wetland)				
Open Drainage	75	75	75	
Culvert (tight pipe)	25	35	35	
Culvert opening	50	75	75	
Catch basins	35	35	35	
In ground pools	25	35	50	10
Private well, on -site	75	125	75	
Private well, off-site	75	125	75	
Community well	200	200	200	
Reservoirs	75	75	75	
Municipal Well	400	400	400	400
Water line, pressure	10	25	25	10
Water line, suction	50	75	75	50
Property line	35	35	35	35
Foundations With drains Full (no drains) Slab (no drains)	25 5 5	35 10 5	35 10 5	
Top of natural embankment or natural steep slope	5	20	20	
Interceptor drains, leaching area Below finished grade Above finished grade	50 35	75 35	75 35	75 35
Property line	35	35	35	03/30/09